BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

Name of Work : Improvements to Roads at ward No. 07, Byatarayanapura in Sanjeevininagara.

Sl. No.	Approved Qty.	Description	Unit	Approved Rates of KRIDL	
				In Figures	In Words
1	60.00	KSRB 2-2.1: Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specification. (Page No.5 item No.2.3) 2012-13 SR	cum	135.00	Rupees One Hundred Thirty Five Only
2	6.00	KSRB: 1-1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.(P.No.12, I.No.4.3 of PW,P&IWTD S.R 2012-13)	cum	3884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
3	21.60	KSRB - 5.2.3: Providing and constructing granite size stone masornry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No.25, I.No.5.6 of PW, P&IWTD SR 2012-13)	cum	2761.56	Rupees Two Thousand Seven Hundred Sixty One and Fifty Six Paise Only
4	48.00	KSRB - 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with CM 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.119, I.No.15.1 of PW, P&IWTD SR 2012-13)	Sqm	71.39	Rupees Seventy One and Thirty Nine Paise Only
5	3.60	KSRB - 4-1.6: Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (P.No.12, I.No.4.6 of PW, P&IWTD SR 2012-13)	cum	4409.64	Rupees Four Thousand Four Hundred Nine and Sixty Four Paise Only
6	24.00	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications. Specification No KBS 4.6.2. (Page No.17 item No.4.30) SR 2012-13	Sqm	315.36	Rupees Three Hundred Fifteen and Thirty Six Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Rates of KRIDL	
				In Figures	In Words
7	8.28	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC Works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3 with all lead and lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns Staircase and Roof with M-20 (1:1.5:3) (Cement 320kg/cum) (Page No.19 item No.4.49.1) SR 2012-13	cum	5639.76	Rupees Five Thousand Six Hundred Thirty Nine and Seventy Six Paise Only
8	7.45	KSRB 4.9.2: Providing TMT. Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, lobour, HOM of machinery complete as per specifications. (Page No. 19 item No.4.46) SR 2012-13	Qtl	7323.48	Rupees Seven Thousand Three Hundred Twenty Three and Forty Eight Paise Only
	716.50	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 168 Item No. 20.18) SR 2012-13	cum	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
9	3005.00	KSRRB 500-8: Providing and applying tack coat on granular surface treated with primer at 7.5kg per 10 sqm heating bitumen in boiler fitted with spray set (excluding cleaning of road surfacr) including cost of all materials labour HOM of Machineries complete as per specifications P-173, Item - SR 2012-13	Sqm	19.66	Rupees Nineteen and Sixty Six Paise Only
10	90.15	KSRRB M500-18. Providing and laying semi dense bituminous concrete 30 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (Grading II)(P. 175, Item No. 21.20.6) SR 2012-13	cum	9138.96	Rupees Nine Thousand One Hundred Thirty Eight and Ninety Six Paise Only
11	89.10	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	cum	58.32	Rupees Fifty Eight and Thirty Two Paise Only
12	891.00	Removing BS Slab of drain and stacking.	Sqm	44.47	Rupees Forty Four and Forty Seven Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Approved Rates of KRIDL	
				In Figures	In Words
13	801.00	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	63.00	Rupees Sixty Three Only
14	89.10	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	315.36	Rupees Three Hundred Fifteen and Thirty Six Paise Only
15	149.10	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	81.00	Rupées Eighty One Only

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92